



WAREHAM WATER POLLUTION CONTROL FACILITY

6 Tony's Lane
Wareham, MA 02571
Telephone (508) 295-6144
Fax (508) 291-0155

#14-IFB-003

COATING SYSTEM FOR SECONDARY CLARIFIERS (2)

November 7, 2014

PROJECT: Coating System for Secondary Clarifiers (2)
DATE ISSUED: October 30, 2014

ADDENDUM NO. 4

The specification documents for the above-referenced project are hereby amended and/or clarified as per the particular listed below:

Scope of Work

- 1. Epoxy termination on the Clarifiers' floors. A cut should be made prior to abrasive blast cleaning in order for it to be profiled the required CSP4.**
- 2. The coating of the rake arms, influent structure and baffle are not to be included in the scope of work.**
- 3. The metallic scum trough shall be blasted as specified.**
- 4. All other components not being blasted shall be protected from abrasive blast damage.**

**Epoxy Termination Detail on Clarifier Floor
(attached)**

***BIDDER MUST ACKNOWLEDGE RECEIPT OF THIS ADDENDUM BY SIGNING
BELOW AND INCLUDING THIS ADDENDUM IN THEIR BID SUBMITTAL.***

Signature of Authorized Bidder

Date



WAREHAM WATER POLLUTION CONTROL FACILITY

6 Tony's Lane
Wareham, MA 02571
Telephone (508) 295-6144
Fax (508) 291-0155

GPI GREENMAN - PEDERSEN, INC.
ENGINEERING AND CONSTRUCTION SERVICES

