



CONTRACTOR QUESTIONS THIS DOCUMENT IS NOT PART OF THE ADDENDUM

March 8, 2021

Project	Narrows Pump Station Bypass Installation	Project No.	11221503
Owner	Town of Wareham, MA	Date of Pre-Bid Meeting	March 3, 2021
Contract No.	2020-WW-2		

The following is a summary of the proposed work discussed at the mandatory Pre-Bid Meeting on March 3, 2021 at the Narrows Pump Station site. This is NOT part of the addendum. This is for informational purposes only.

1. Existing force main is a 16-inch force main and there are no other known force mains connected to this force main.
2. Groundwater is expected to be 3 to 4 feet below grade and dewatering is to be expected.
3. Filter bag is to be used for dewatering and discharge is to be sent to the catch basin to the west of the pump station.
4. No stockpiled material is to be left overnight.
5. Test run with septage trucks is to be completed at night.
6. Town to pay for the septage trucks, but the Contractor is responsible for coordinating the septage trucks.
7. Per the plans the 6-inch cam-lock quick connect is to be located in the pavement and the flange for the pig launch will be installed above grade within the pump station site.
8. Town is to operate the pump station and all valves necessary during construction.

The following are questions received from the contractors at or prior to the mandatory Pre-Bid Meeting on March 3, 2021 at the Narrows Pump Station site. This is NOT part of the addendum. This is for informational purposes only. Please note that some questions are paraphrased.

1) Does the project need to comply with American Iron and Steel requirements?

GHD Response: The project does not have American Iron and Steel requirements, please see Addendum No. 1.

2) Is the 6-inch pipe connecting to the existing sewer manhole to be installed at the same elevation as the existing pipes in the manhole?

GHD Response: Yes, the elevation is to match the elevation of the outlet pipe going to the wet well. This can be adjusted in the field, with Engineer approval, as necessary depending on the elevation of the existing force main.



SIGN IN SHEET
THIS IS NOT PART OF THE ADDENDUM

NARROWS PUMP STATION BYPASS INSTALLATION
PRE-BID MEETING
WEDNESDAY MARCH 3, 2021 10:00 AM
1 MERCHANTS WAY WAREHAM, MA (NARROWS PS SITE)

INITIAL	NAME	AFFILIATION	ADDRESS	PHONE	FAX	CELL	EMAIL
	Guy Campinha	Wareham Sewer Department	6 Tonys Lane Wareham, MA 02571	508-295-6144	508-291-0155		gcampinha@wareham.ma.us
	Russ Kleekamp	GHD Inc.	1545 Iyannough Road, Hyannis, MA 02601	774-470-1647	774-470-1631	774-313-8663	Russell.Kleekamp@ghd.com
	Craig Curtin	GHD Inc.	1545 Iyannough Road, Hyannis, MA 02601	774-470-1653	774-470-1631	508-292-0310	Craig.Curtin@ghd.com
	N. Granese	N. Granese & Sons, Inc.	59 Jefferson Ave Salem, MA 01970	781-592-8121			info@ngranese.com
	David Dow	RFS Corp	130 Liberty St Brockton, MA 02301	508-328-2819		508-660-8700	rsaccone@rfscontracting.com
	Rod Brown	Pride Environmental	70 N Main St Berkley, MA	508-880-6009		508-328-2391	rod@prideenvironmental.com
	Mike Oliveira	Oliveira Construction Inc.	1100 Grand Army of the Republic Hwy Somerset, MA	508-672-4598		508-326-9727	Oliveira80@msn.com
	Tim Parlato	D'Allessandro Corp	254 Pleasant St W. Bridgewater, MA	617-413-6022			estimating@dallessandro.com
	Mike Biszko	Biszko Building Systems Inc.	20 Development Street Fall River, MA	508-679-0518			biszko@biskocorp.com

