



# ADDENDUM NO. 1 TO CONTRACT DOCUMENTS

Project	Sewer Bypass Installations at Cohasset Narrows & Hynes Field Pumping Stations	Project No.	11186079
Owner	Town of Wareham, MA	Federal Project No.	
Contract No.	2019-001	Date	

To All Contractors:

Contractors submitting proposals for the above-named project shall take note of the following changes, additions, deletions, clarifications, etc., in the Contract Documents, which shall become a part of and have precedence over anything contrarily shown or described in the Contract Documents, and all such shall be taken into consideration and be included in the Contractor's bid proposal.

*Please see attached pages.*

The return receipt requested with this communication is to be deemed evidence that the bidder has received this addendum and has followed the instructions outlined therein.



*Marc Drainville*, P.E., BCEE  
 \_\_\_\_\_  
 Marc R. Drainville, Principal



ITEM NO. 1.

Section 01380

- A. Under paragraph 1.03, REMOVE:

“Item C – Take aerial photographs of the completed project”

ITEM NO. 2.

Section 01026

- A. DELETE paragraph 2 of Bid Item B-1 description and REPLACE with the following:

“Contractor is required to **coordinate all required septic haulers / pumping trucks** to maintain operations of the Town’s sewer system and infrastructure that leads to this pumping station. Contractor shall **pump** all sewer flow from the upstream manhole to the pumping station.”

- B. DELETE paragraph 2 of Bid Item A-1 description and REPLACE with the following:

“Contractor is required to **coordinate all required septic haulers / pumping trucks** to maintain operations of the Town’s sewer system and infrastructure that leads to this pumping station. Contractor shall **pump** all sewer flow from the upstream manhole to the pumping station.”

ITEM NO. 3.

Section 01500

- A. Under paragraph 1.02A, MODIFY to read:

“Provide temporary equipment including **coordination with septic haulers / pumping trucks**, piping, valves, bulkheads, electrical equipment, and all system components necessary to maintain the existing facilities in service during construction.”

ITEM NO. 4.

Section 01500

- A. Under paragraph 2.01B, MODIFY to read:

“Buried Ductile Iron Pipe - ANSI A21.51/AWWA C151 - Ductile iron pipe material, thickness design conforming to ANSI A21.50/AWWA C150, Pressure Class 350, rubber gasket restrained push-on joints and fittings conforming to ANSI 21.11/AWWA C111 and fittings conforming to **ANSI /AWWA C153/A21.53-00**”